

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Oxy USA, Inc.  
Address: PO Box 2528 Liberal KS. 67905  
Phone: (620) 629-4200 Operator License #: 5447  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1-13-05 (Date)  
by: Steve Middleton (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Topeka Depth to Top: 2880 Bottom: 3056 T.D. 5390  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-129-10257-00-01  
Lease Name: Fulkerson B  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - SW-NE  
1995 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 6 Twp. 35 S. R. 41  East  West  
County: Morton  
Date Well Completed: 11-16-60 (original)  
Plugging Commenced: 1-14-05  
Plugging Completed: 1-18-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1482	-
				4 1/2	3454	1516

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 400 lb hulls to 20 sx cmt (lost plug out perms). Mixed 300 lb hulls to 20 sx to plug perms from 2880 to 2680. Shot & pulled to 1500. Circ. hole w/mud & mixed 50 sx 1500 to 1350 30 sx 350 to 250 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905  
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 25 day of Feb, 2005

Anita Peterson My Commission Expires: Oct. 1, 2005  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

