

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-23,127 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Baird Oil Company OPERATOR'S LICENSE NO. 5352

ADDRESS P.O. Box 428 Logan, KS 67646 PHONE # (913) 689-7457

LEASE (FARM) Gartrell WELL NO. #4 WELL LOCATION NE SW SW COUNTY Rooks

SEC. 22 TWP. 6S RGE. 20 (E) or (W) TOTAL DEPTH 3678' PLUG BACK TD _____

Check One:

OIL WELL ___ GAS WELL ___ D & A x SWD or INJ WELL ___ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 242' CEMENTED WITH 60-40pozmix SACKS 170

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD x POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 3673' w/25 sx; 2nd plug @ 1775' w/25 sx; 3rd plug @ 1040' w/100 sx; 4th plug @ 270' w/40 sx; 5th plug @ 40' w/10 sx; 60-40 pozmix 6% gel, 1/4# Flocel per sack.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not explain.) sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11-14-90 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

JAN 2 1991
1-2-91
CONSERVATION DIVISION
Wichita, Kansas
DATE: _____

SIGNED: Jack K. Wharton
(Operator or Agent)

12-13-90