

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-009-15237-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/13/38

Well Operator: Zinszer Oil Company, Inc. KCC License #: 6239 ^{6/05}
(Owner / Company Name) (Operator's)

Address: P.O. Box 211 City: Hays

State: Kansas Zip Code: 67601 Contact Phone: (785) 625-9448

Lease: Frees/Burmeister (Frees) Well #: 13 (also #1) Sec. 3 Twp. 17 S. R. 11 East West

SW - SW - NE Spot Location / QQQQ County: Barton

2970 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13" Set at: 317' Cemented with: no record Sacks

Production Casing Size: 7" Set at: 3320' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1914 (G.L. / K.B.) T.D.: 3333 PBTD: 3330 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pull 7" casing, as Hays District recommends.

RECEIVED

is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

FEB 24 2005

If not explain why? Old well

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Perry S. Henman

Phone: (785) 625-9448

Address: P.O. Box 211 City / State: Hays, Kansas

Plugging Contractor: Quality Well Service KCC License #: 31925 ^{8/05}
(Company Name) (Contractor's)

Address: Lyons, Kansas 67554 Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): as weather and rig schedule permit.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator ~~and Agent~~


Date: 2/21/05 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bank Bldg, Wichita, Kansas.

W. L. LOG PLOTTED
 CHECKED C. M. LOG
 FILED WITHOUT




No. 1

DERBY OIL CO.
 Frocs No. 13

also #1
 SEC. 3 T. 17 R. 11W.
 S. 20 NE

Total Depth. 3333
 Comm. 3-13-38 Comp. 4-3-38
 Shot or Treated.
 Contractor. Earl Carey.
 Issued. 6-4-38

County Barton.



Elevation. 1914

Production. Pot. 2031 B.
 Nat.

CASING.
 13" 317' 7" 3320'

Figures Indicate Bottom of Formations.

cellar	8	shale	3320
shale and shells	175	Top of Siliceous lime	3320
sand	260	Siliceous lime	3330
red bed and shells	325	very porous and sat. with oil full Rec.	
shale and shells	430	Standardized with 6" tools.	
shale & lime shells	750	cleaned out from 3320 to 3330 with 6"	
shale and shells	983	tools and drilled to 3333.	
lime and shells	1161	cleaned out to 3333 and swabbed.	
salt	1390	On swab test the well made 85 bbls	
shale	1420	oil per hour.	
lime	1460	siliceous lime	3333-1419
broken lime shale	1524	Total Depth.	
shale	1660		
broken lime & shale	1725	GEOLOGICAL TOPS.	
lime	1770	Top Ft. Riley	1671 + 243
shale	1790	Base Florence Flint	1810
broken lime	1859	Top Lansing	3055 - 1141
shale and shells	1890	Base K.C.	3318 - 1407
lime	1910	Top Arbuckle	3320 - 1406
shale	1995		
lime	2089		
shale	2375		
broken lime & shale	2430		
lime	2545		
shale and shells	2581		
shale	2635		
lime & shale	2755		
lime	2985		
shale	3055		
lime soft	3070		
lime	3100		
broken lime & shale	3155		
lime soft porous	3167		
lime	3230		
broken lime & shells	3300		
Cored.			
K.C. lime	3318 - 1407		1016
Base K.C. lime	3318		1130

RECEIVED
 FEB 24 2005
 KCC WICHITA

March 7 1938
 7 1/2

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor. Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Zinszer Oil Co., Inc.
PO Box 211
Hays, KS 67601-0211

February 25, 2005

Re: BURMEISTER (FREES) #13
API 15-009-15237-00-00
SWSWNE 3-17S-11W, 2970 FSL 2310 FEL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor