

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15- 155-21,179-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_

Well Operator: Globe Operating, Inc. KCC License #: 6170 6/05

Address: P.O. Box 12 (Owner/Company Name) City: Great Bend, (Operator's)

State: Kansas Zip Code: 67530 Contact Phone: (620) 792 7607

Lease: Bontrager Well #: 1 OWWO Sec. 3 Twp. 25 S. R. 9  East  West

50' N. - C-SW - SE - SE Spot Location / QQQQ County: Reno

380 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 231 Cemented with: 150 Sacks

Production Casing Size: 5-1/2" Set at: 4003 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_ Perfs: 3840-48

Elevation: 1682 ( G.L. /  K.B.) T.D.: 4005 P.B.T.D.: 3942 Anhydrite Depth: \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): \_\_\_\_\_

According to the rules & regulations of the State of Kansas.

RECEIVED

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

FEB 24 2005

If not explain why? Log Unavailable Copy of well card attached. KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Richard Stalcup Phone: (620) 793 - 2891 (cell)

Address: P.O. Box 12 City / State: Great Bend, Kansas 67530

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529 9/05

Address: P.O. Box 467 Chase, Kansas 67524 Phone: (620) 793 - 2943 (Contractor's)

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-23-05 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RAYMOND OIL CO  
WICHITA KS 67201

3-25 -09W  
50'N, C SW SE SE

#1 BONTRAGER OWWO

site: 2-3/4 N & 1-1/2 E OF LANGDON KS	city: RENO	API 15-155-21179-A
contr: DUKE DRILLING #2	field: LANGDON NE EXT (1/4 NW)	
geol: ART SCHOENHOFER / MIKE RAYMOND		
fr date 05/19/93	spd date 06/21/93	drig comp 06/24/93
	card issued 07/19/93	last revised 07/19/93


ELEV: 1691 KB, 1682 GL LOG
tops.....depth/datum
HEEB.....3135 -1444
BR LM.....3326 -1635
LANS.....3346 -1655
STARK.....3608 -1917
BKC.....3700 -2009
CHER.....3800 -2109
MISS.....3843 -2152
MISS LM.....3898 -2207
KIND.....3913 -2222
RTD OLD.....3940 -2249

IP status:  
OIL, P 3 BO & 50 BWP, MISS 3840-3848 ,  
NOTE: 5/19/93 - KCC API 15-155-21179-0001; INFO REL:  
11/16/92 - WAS D & A - TIGHT HOLE  
OLD INFO: OPERATOR WAS HONEY OIL CO, 1  
BONTRAGER, SPD 09/19/91 , 09/24/91 8-5/8" 231 / 150  
SX (ALT 1), D&A, KIND , 09/24/91 (CARD ISSUED  
10/21/91 )  
CONTR: DUKE DRILLING  
GEOL: JOE BAKER  
NO CORES OR DSTS  
TRGT ZN: VIOLA , PTD 3900 (VIOLA)  
NEW INFO: FR 05/19/93 , RE-ENTERED 06/21/93 WSH  
DWN TO 3940, RAN DSTS (1-3) DC 06/24/93 CSG: SET  
5-1/2" 4003 / 175 SX

COPYRIGHT 1993  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

RAYMOND OIL CO  
WICHITA KS 67201

3-25 -09W  
50'N, C SW SE SE

#1 BONTRAGER OWWO

ELEV ON REWORK WAS: 1690 KB, 1682 GL  
NO CORES  
DST (1) 3815-3854 (CHER, MISS), / 45-60-90-60, GTS/3", GA 526 MCFGPD DECR TO 222  
MCFGPD, REC 1116' HM & GCO, 464' CLEAN OIL ISIP 1170# FSIP 1118# IFF 45# -373# FFP  
352# -427# BHT 118 °  
DST (2) 3858-3868 (MISS), / 45-60-90-60, REC 50' HDM, NS ISIP 160# FSIP 640# IFF 45#  
-160# FFP 90# -85# BHT 118 °  
DST (3) 3875-3940 (MISS), / 45-60-90-60, 2820' GIP, REC 120' G & OCM, 120' G & OCWM, 60'  
G & OCMW, 240' W ISIP 1223# FSIP 1223# IFF 107# -107# FFP 160# -213# IHP 120#  
TRGT ZN: MISS, PTD 3942 (KIND), MICT - CO, PF (MISS) 3840-3848, W / 1 SPF, SWB 4.6 BOPH,  
AC 500 GAL (7.5% MA), SWB 4 BOPH, POP, P 8 BO & 90 BWP, DECR TO 3 BO & 50 BWP,  
7/2/93

RECEIVED  
FEB 24 2005  
KCC WICHITA

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Globe Operating, Inc.  
PO Box 12  
Great Bend, KS 67530

February 25, 2005

Re: BONTRAGER #1-OWWO  
API 15-155-21179-00-01  
SWSESE 3-25S-9W, 380 FSL 990 FEL  
RENO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000

Sincerely



David P. Williams  
Production Supervisor