

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-159-22447-00.00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: Don Fox  
(owner/company name)

KCC LICENSE # 7079 <sup>6/05</sup>  
(operator's)

ADDRESS: 2700 Westminister CITY: Hutchinson  
STATE: Kansas ZIP CODE: 67502 CONTACT PHONE: 620-662-2862  
LEASE: Volkland WELL#: B-5 Section 27 Township 18s Range 9w  
C S/2 NW SW SPOT LOCATION/QQQQ COUNTY: Rice

1650 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
660 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 213' KB CEMENTED WITH 165 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1710 G.L. 1719 K.B. T.D. 3265 PBD \_\_\_\_\_ Anhydrite Depth 373  
(Stone Corral Formation)  
CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Plugged well on 01/10/05 as follows: Heavy mud in hole and between all plugs. Plugged using 200 sx of 60/40 Poz, 6% Gel in hole. Bottom plug at 3250' with 35 sx, 2nd plug at 1500' with 35 sx, 3rd plug at 700' with 35 sx, 4th plug at 250' with 35 sx, top plug at 60' with 60 sx cemented to surface. Rathole with 15 sx, no mousehole.  
Job complete at 2:30 pm on 01/10/05. Allied Cementing ticket #20239. KCC notified of plugging on 01/11/05.  
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Name: Gary Pugh /Gary Talbott Phone#: (620) 672-9508  
Address: P.O. Box 1006 City: Pratt State: Kansas  
PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142 <sup>6/05</sup>  
(company name) (contractor's)  
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 2:30 pm on 01/10/05  
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 01/10/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott  
(signature) Gary M. Talbott, Agent for Operator

RECEIVED  
JAN 18 2005  
KCC WICHITA

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Volkland B-5

**LOCATION:** C S/2 NW SW  
**API:** 15-159-22447-00.00

Section 27 T 18s R 9w  
Rice County, Kansas

**OWNER:** Don Fox  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 04-Jan-05  
**COMPLETED:** 10-Jan-05

**TOTAL DEPTH:** **DRILLER** 3265 FEET  
**LOGGER** No Log FEET

**Ground Elevation:** 1710  
**KB Elevation:** 1719

### LOG

0 -	4 FEET	Top Sand
4 -	22 FEET	Clay
22 -	87 FEET	Sand, Rock and Shale
87 -	180 FEET	Shales, Sand and Clay
180 -	700 FEET	Redbeds
700 -	373 FEET	Shales
373 -	1180 FEET	Shales and Salt
1180 -	3250 FEET	Limestone, Shale and Dolomite
3250 -	3265 FEET	Arbuckle

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 7:30 am on 01/04/05. Drilled 12-1/4" hole to 213'. Ran 5 joints of 8-5/8" surface casing, tally 216' set at 213' KB. Cemented with 165 sx 70/30 Poz; 2% Gel, 3% CC, Plug down at 1:45 pm on 01/04/05 by Allied Cementing. Ticket #20563. Cement did circulate. Strapped bottom 3 joints, welded collars next 2 joints.

#### Production Casing-5-1/2"

Plugged well on 01/10/05 as follows: Heavy mud in hole and between all plugs. Plugged using 200 sx of 60/40 Poz, 6% Gel in hole. Bottom plug at 3250' with 35 sx, 2nd plug at 1500' with 35 sx, 3rd plug at 700' with 35 sx, 4th plug at 250' with 35 sx, top plug at 60' with 60 sx cemented to surface. Rathole with 15 sx, no mousehole. Job complete at 2:30 pm on 01/10/05. Allied Cementing ticket #20239. KCC notified of plugging on 01/11/05.

### DEVIATION SURVEYS

1-1/4	degree(s) at	213	feet
1-1/2	degree(s) at	3265	feet

RECEIVED  
JAN 18 2005  
KCC WICHITA