

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 135-21427-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Great Plains Petroleum, Inc. KCC License #: 30163 7/04

Address: 221 Circle Drive City: Wichita

State: Kansas Zip Code: 67218 Contact Phone: (316) 685 - 8800

Lease: Rupp Well #: 2 Sec. 33 Twp. 16 S. R. 25 East West

Spot Location / QQQQ - SW - SW County: Ness

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 304 Cemented with: 135 Sacks

Production Casing Size: 4-1/2 Set at: 4545 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Miss. Perfs @ 4495-4500, CIBP @ 4450, Ft. Sc. Perfs @ 4382-85.

Elevation: 2548 (G.L. / K.B.) T.D.: 4545 P.B.T.D.: 4542 Anhydrite Depth: 1980
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Isolate Ft. Scott perfs with CIBP @ 4125' and 2 sx cmt.

Isolate Cedar Hills with CIBP @ 1300'. Pressure test casing to 500#. Perforate @ 1100' to circulate cement past Dakota.

Squeeze with 60 sx over casing capacity if well will not circulate and pump 85 sx down 8-5/8 casing.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 07 2003

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rod Phares

Phone: (316) 685 - 8800

Address: 221 Circle Drive City / State: Wichita, KS

Plugging Contractor: Swift Services Inc. Intzler Trucking Inc. Whitetail Crude, Inc. KCC License #: 31625 32382

Address: P.O. Box 544 Ness City, KS 67560 Phone: (785) 798 - 3641

Proposed Date and Hour of Plugging (if known?): 8:00 AM, Nov. 6, 2003 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/5/03 Authorized Operator / Agent: Rod A. Phares (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

2/04

NOV 07 2003

CONSERVATION DIVISION
WICHITA, KS

WELL LOG

OPERATOR: Liberty Enterprises, Inc.

WELL NAME: Rupp A #2 LOCATION: C. SW SW 33-16S-25W

COUNTY: Ness STATE: Kansas

WELL COMMENCED: March 17, 1978 WELL COMPLETED: March 25, 1978

ELEVATION: 2548 K.B. TOTAL DEPTH: 4545'

PRODUCTION: Mississippi RIG NO: #1

CASING - 8-5/8": 304' with 135 sxs 3% cc 2% gel

4 1/2" ~~SXSDXX~~ 4544' with 150 sxs common 10% salt

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
305'	770'	sands and surface clays	305' 3/4 degree	
770'	1360'	shale and sand		
1360'	1580'	sand		
1580'	1690'	shale		
1600'	1895'	sand and shale		
1895'	2190'	Anhydrite and shale	1936' 1 degree	
2190'	2525'	shale and shells		
2525'	2650'	shale and lime		
2650'	2800'	shale and lime	2795' 2 degrees	
2800'	3030'	lime and shale		
3030'	3235'	lime and shale		
3235'	3402'	lime		
3402'	3530'	lime		
3530'	3750'	lime and shale		
3750'	3898'	lime and shale		
3898'	3950'	lime and shale		
3950'	4105'	lime		
4105'	4175'	lime		
4175'	4310'	lime and shale		
4310'	4410'	lime		
4410'	4477'	lime		
4477'	4490'	lime		
4490'	4503'	lime		
4503'	4545'	lime		

STATE OF KANSAS
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct


PIONEER DRILLING CO., INC.

By [Signature]

SUBSCRIBED AND SWORN TO, BEFORE ME, This 29th day of March 1978.

MY COMM. EXP. SEPT. 6, 1981.

Krystal Schwenn
KRYSTAL SCHWENN - NOTARY PUBLIC



Send to SCC on March 29, 1978