

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BLACK DIAMOND OIL, INC

Address: P.O. BOX 641

Phone: (785) 625-5891 Operator License #: 7076

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/23/04 (Date)

by: HERB DEINES (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: Bottom: T.D. 3729'
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number: 15-163-2249-00-00 (with handwritten 2249)

Lease Name: WYRILL

Well Number: 1

Spot Location (QQQQ): SW - NW - NW -

4290 Feet from North / South Section Line

4950 Feet from East / West Section Line

Sec. 29 Twp. 6S S. R. 20 East West

County: ROOKS

Date Well Completed: 10-24-84

Plugging Commenced: 11/23/04

Plugging Completed: 11/23/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes entries for Arbuckle and Lansing KC formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

PC AT 1886' W/350 SKS CEMENT, DID NOT CIRCULATE, PERF AT 1200'-DID NOT CIRC., PERF AT 1200' WITH 600 SKS CEMENT SQUEEZED AT 3726', RAN TUBING TO 3660', SPOTTED 100 SKS CEMENT AND 500# HULLS, PULLED TUBING TO 1650' CIRCULATED WITH 60 SKS CEMENT, PULLED ALL TUBING AND TOPPED OFF WITH 20 SKS CEMENT, TIED TO 8-5/8 x 4 1/2 SQUEEZED 30 SKS CEMENT, MAX PSI 500# SIP 500#, TOTAL 210 SKS 60/40 POZMIX, 10% GEL AND 500# HULLS

Name of Plugging Contractor: EXPRESS WELL SERVICE License #: 6424 RECEIVED

Address: JAN 31 2005

Name of Party Responsible for Plugging Fees: BLACK DIAMOND OIL, INC. KCC WICHITA

State of KANSAS County, ELLIS, ss.

KENNETH VEHIGE (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 641, Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 27th day of January, 20 05

[Handwritten Signature] My Commission Expires: 7-18-07