

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.

Address: 3101 N. Rock Rd. Suite 125 Wichita, Ks.

Phone: (316) 636-5155 Operator License #: 31389 67226

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Gary (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. 3180

API Number: 15-159419016-00-00

Lease Name: Pickerill

Well Number: 3

Spot Location (QQQQ): NE - SE - NE

1650 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 24 Twp. 18 S. R. 8 East West

County: Rice

Date Well Completed:

Plugging Commenced: 1-19-05

Plugging Completed: 1-20-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for 10-3/4" and 7" casing.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Set bridge plug @2775' with 3 sacks cement on top, perforated casing @1050', 700' and 275'. Ran 2-3/8" tubing to 1050', pumped 50 sacks cement, pulled tubing up to 700', pumped 50 sacks cement, pulled up to 275' and circulated 100 sacks to surface. Layed rest of tubing down and topped off with 10 sacks. 60/40 pos 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 28th day of January, 2005

[Handwritten Signature] My Commission Expires:

NOTARY PUBLIC - State of Kansas IRENE HERZBERG My Appt. Exp. 5-24-05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Initials]