

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cabot Oil & Gas Corporation
 Address: 600 17th Street, Ste. 900N, Denver, CO
 Phone: (303) 226-9443 Operator License #: 6120
 Type of Well: Oil & Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 12-16-04 (Date)
 by: Ken Jehlik (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 4409' Bottom: 4412' T.D. _____
Morrow Depth to Top: 5692' Bottom: 5696' T.D. 6230'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-20071-00-00
 Lease Name: Freeman
 Well Number: 1
 Spot Location (QQQQ): SW-SW-NE-NE
1250 Feet from North / South Section Line
1250 Feet from East / West Section Line
 Sec. 18 Twp. 33 S. R. 33 East West
 County: Seward
 Date Well Completed: 11-5-69 1-14-1970
 Plugging Commenced: 12-17-04
 Plugging Completed: 12-20-04

KCC
BEM
1-31-05
RBDMS
CP 2/3
KCC
BEM
1-31-05
RBDMS
ACD

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	Oil	4409'	4412'	8-5/8"	1,622'	---
Morrow	Gas	5692'	5696'	5-1/2"	5,818'	2,477'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rosel set CIBP + 2 SX cmt. 4380' to 4360'. Shot & pulled 5-1/2 to 1,650'. Circ. hole w/mud & mixed 50 sx cmt. 1650' to 1500'
 30 sx 720' to 620', 10 sx 40' to 0'. Capped 8-5/8" 3 ft. below G.L.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 27 2005

Name of Plugging Contractor: Sargent & Horton Plugging, Inc. License #: 31151
 Address: Rt. 1, Box 49 BA, Tyrone, OK 73951-9731


CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Cabot Oil & Gas Corporation
 State of Colorado County, Denver, ss.

Jay Vashler (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay Vashler
 (Address) 600 17th Street, Ste. 900N, Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 25 day of January
Jean A. Arnold My Commission Expires 12-22-06
 Notary Public My Commission Expires 12/22/2006



Bm