

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vess Oil Corporation

Address: 8100 E. 22nd. St. North Wichita, Ks. 67226

Phone: (316) 682-1537 Operator License #: 5030

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 4397'

API Number: 15-185-13264-00-00

Lease Name: Thurrow "A"

Well Number: 1

Spot Location (QQQQ): SE SE SW

330' Feet from ☐ North / ☒ South Section Line

2970' Feet from ☐ East / ☒ West Section Line

Sec. 36 Twp. 24S S. R. 15 ☐ East ☒ West

County: Stafford

Date Well Completed: 10-9-59

Plugging Commenced: 12-29-04

Plugging Completed: 12-30-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	290'	None
				5-1/2"	4392'	1260'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4340' and 5 sacks cement. Pumped 10 sacks
gel down annulus to kill gas flow. Cut casing loose @1260', pumped 50 sxs.
cement, pulled up to 960', pumped 14 sxs. gel & 75 sxs. cement, pulled up to
330', pumped 100 sxs & circulated to surface. Topped off w/20 sxs. cement.
Plugging Complete. 60/40 pos, 6% gel.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 9th day of February, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 11 2005
KCC WICHITA