

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hupfer Operating, Inc.
Address: P.O. Box 216 Hays, Kansas 67601
Phone: (785) 628 8666 Operator License #: 30380
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or, ENHR)
The plugging proposal was approved on: _____ (Date)
by: Patrick Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 3379'

API Number: 15-009-21,444-00-00
Lease Name: Deutsch
Well Number: 6
Spot Location (QQQQ): _____ - SE - SE - NW
2970 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 9 Twp. 16 S. R. 13 East West
County: Barton
Date Well Completed: _____
Plugging Commenced: 1-17-05
Plugging Completed: 1-19-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In / Pulled Out
				8-5/8"	359' / None
				4-1/2"	3376' / 2205'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3300' and 5 sacks cement. Cut casing loose @2205', pulled up to 1600', pumped 75 sacks cement W/300# hulls, pulled up 925', pumped 40 sacks cement & 100# hulls, pulled up to 500', pumped 20 sacks cement W/100# hulls, pulled up to 150' & circulated 35 sacks cement, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Hupfer Operating, Inc.

State of Kansas County, Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso **RECEIVED**

(Address) P.O. Box 467 Chase, Kansas 67524 **FEB 25 2005**

SUBSCRIBED and SWORN TO before me this 22nd day of February

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202