



15-163-20126-0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlich of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Herndon Drilling Co.

Complete Address: Box 489 Tulsa, Okla.

Lease Name: Wiltrout Well No. 1

Location: C NW NW Sec. 10 Twp. 6 Rge. 20 (E)(W) X

County: Rooks Total Depth 3685 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 - 1968

CONSERVATION DIVISION
Wichita, Kansas

10-1-68

Very truly yours,

Leo J. Mearns
Conservation Division Agent