



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 28 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 10-28-68

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Branum of Branum Oil Co. has this date requested permission to plug the following described well:

Mr. Branum guarantees payment of the plugging fee.

Operator's full Name: Branum Oil Co.

Complete Address: Russell, Ks.

Lease Name: Wyrill Well No. 1

Location: NW NW Sec. 29 Twp. 6 Rge. 20 (E)(W) X

County: Rooks Total Depth <sup>2270'</sup> 2265' Oil Well

Gas Well      Input Well      SWD Well      D & A      Lost Hole XX

Mr. Branum was instructed to plug the well as follows:

Set 25 sc 4% cc plug at 600' thru drill pipe. Check fillup

Displace 25 sc cmt thru drill pipe.

Set cementing plug at 200' and displace 25 sc cmt thru drill pipe.

Mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base of cellar

Plug rat hole with 2 sc cement.

Very truly yours,

Leo J. Messing  
 Conservation Division Agent