

State of Kansas



15-163-20091-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1968

CONSERVATION DIVISION
Wichita, Kansas

1-29-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of L. J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: L. J. Dreiling & Sons, Inc.

Complete Address: Victoria, Ks.

Lease Name: Benoit Well No. 1

Location: NW NW SW Sec. 29 Twp. 6 Rge. 20 (E)(W) X

County: Rooks Total Depth 3840 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sc cement thru drill pipe. Heavy mud to 150' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Geo F. Messing
Conservation Division Agent