

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-009-21,833-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Comp. 3-5-80

Well Operator: Robinowitz Oil Company (Owner/Company Name) KCC License #: 6883 ^{6/05} (Operator's)

Address: 7130 S. Lewis, Suite 910 City: Tulsa

State: Oklahoma Zip Code: 74136 Contact Phone: (918) 481-7196

Lease: Luerman-Weeks Well #: 1 Sec. 18 Twp. 16 S. R. 13 East West

SE NW SW Spot Location / QQQQ County: Barton

1650 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # ENHR Docket # Other:

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 8-5/8" Set at: 438' Cemented with: 285 Sacks

Production Casing Size: 5-1/2" Set at: 3389' Cemented with: 165 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 3361-64, 3374-76

Elevation: 1930 (G.L. / K.B.) T.D.: 3390' PBTD: 3370' Anhydrite Depth: (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

According to the rules & regulations of the State of Kansas.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Unavailable

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations:

Don Degenhardt Phone: (620) 793-2299 (Cell)

Address: City / State: Hitschmann, Kansas

Plugging Contractor: Mike's Testing & Salvage, Inc. (Company Name) KCC License #: 31529 ^{9/05} (Contractor's)

Address: P.O. Box 467 Chase, Ks. 67524 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-1-05 Authorized Operator / Agent: Gene Stenberg (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 02 2005
KCC WICHITA

WELL SKETCH

WELL: Luerman-Weeks No. 1 DATE: February 28, 2005

LOCATION: SE NW SW 18-16-13W, Barton County, Kansas

ELEVATIONS: GL: 1930' ZERO IS 5' ABOVE GROUND LEVEL

Completed: 3/5/80 API #: 15-009-

Initial Potential: 60 BOPD/60 BWPD, Arbuckle @ 3374'

8 5/8" Casing @ 438' w/ 285 Sx

Probable Dakota Leak

No tubing or rods in well.

12/20/2004 – Set RBP @ 3015'. Test casing above RBP. Casing has multiple holes above 3015'. Pull RBP. Well to be plugged.


Arbuckle Perfs: 3361-64' (June, 1988)

CIBP @ 3370' (June, 1988)

Arbuckle Perfs: 3 jets @ 3374' (Original Completion)

3379' Drilled Out T.D.

5 1/2" ??# Casing @ 3389' w/ 165 Sx



3390' TD

RECEIVED
MAR 02 2005
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Robinowitz Oil Company
7130 S. Lewis, Ste 910
Tulsa, OK 74136

March 03, 2005

Re: LUERMAN / WEEKS #1
API 15-009-21833-00-00
SENWSW 18-16S-13W, 1650 FSL 990 FWL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor