

DISTRICT CONSERVATION AGENT'S REPORT

15-163-01108-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 48-43

LOCATION CN¹/₂ NW NW

SEC. 9 TWP. 6 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Steele

Operator Colorado Oil & Gas Address Box 1030 Wichita, Kans

Field _____ County Rooks

Total Depth 3639 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 161' circulated with cement - 4 1/2" 3602' with 85 sax
cement behind.

Sand to 3590', set 4 sax cement with dump bailer, pulled 1400' 4 1/2"
to 1000', circulated hole with heavy mud (25 sax Gel), displaced
25 sax cement through 4 1/2" at 500', heavy mud to 155', displaced
20 sax cement through 4 1/2" at 155', heavy mud to 25', set rock and
filled hole to 0' with cement.

Edon L...
District Conservation Agent

Date 10-4-57

RECEIVED
OCT 9 1957
CONSERVATION DIVISION
Wichita, Kansas
10-9-57

PLUGGING
FILE SEC 9 T. 6 R. 20 W
BOOK PAGE 48 L. E. 43