

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

Handwritten initials/signature

15-163-02386-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 78-31 Location: NW NE NW
County: Rooks Sec. 9 Twp. 6 Rge. 20 (E) (W) X
Name of Field or Pool: _____ Total Depth: 3641

I have this date completed supervision of plugging of:

Well No. 1 Lease Steele
Operator's Full Name Barnett Oil Co
Complete Address: 411 1st Natl Bk Bldg Wichita,
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kans License No. 49

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A
If well is a rotary drilled dry hole did operators wait for you to arrive _____
If yes how long _____ Reason: _____

Operation Completed: Hour 10 AM Day 2 Month 2 Year 58

The above well was plugged as follows:

8 5/8" at 178' circulated with cement - 5 1/2" 3640 with 125 sax cement
behind - top perforations 3608'
Filled with sand to 3600', set 4 sax cement with dump bailer, pulled
2833' 5 1/2" to 680', circulated hole with heavy mud through 5 1/2" (Gel),
displaced 20 sax cement through 5 1/2" at 680', heavy mud to 160',
displaced 20 sax cement through 5 1/2", heavy mud to 35', set rock and
10 sax cement to bottom cellar. Used pump truck

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edmond Lee*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1958 2-7-58

Reviewed: *J. Lewis Bank*
Field Supervisor

Signed: _____
CONSERVATION DIVISION
Well Plugging Supervisor

Remarks:

PLUGGING
FILE SEC. 9 T. 6 R. 20
BOOK PAGE 78 LINE 31