

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -163-21, 063-00-00 (of this well)

Operator's Full Name GEODESSIA CORP. - W.E. CARL, HANN BROS. ASSOCIATED PET. CONSULTANTS

Complete Address SUITE 600 ONE MAIN PLACE - WICHITA, KS.

Lease Name HANSEN FOUNDATION Well No. "A" #2

Location C-NE-SW Sec 12 Twp. 6 Rge. 20 (E) (W) W

County ROOKS Total Depth 3650 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor PIONEER DRIG. CO, INC.

Address 308 WEST MILL, PLAINVILLE, MS. License No. \_\_\_\_\_

Operation Completed: Hour 6:45 PM Day 19th Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 240 FE SP CUL. w/ 110 ST COMMON 2% GEL. - 3% CA.-CL.  
ORDERED 110 ST 50/50 Permox 6% GEL + 8 5/8 PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1 ST PLUG. @ 860 FE w/ 70 ST CMT.

2 ND PLUG. @ 240 FE w/ 25 ST CMT

3 RD PLUG. -> SOLID BRIDGE HULL'S PLUG @ 40 FE 0 w/ 10 ST CMT

5 ST IN RAT HOLE

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1980  
CONSERVATION DIVISION  
Wichita, Kansas  
7-22-80

CEMENTED BY ALLIED ENT

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-23-80

WELL NO. 2654-W

Signed: Marion Schmidt  
Well Plugging Supervisor