

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,860 - 00-00 (of this well)

Operator's Full Name Brandt Oil Co.

Complete Address 1103 Douglas Bldg., Wichita, Kansas

Lease Name Hansen Estate Well No. 2

Location 150'W of SE NW NE Sec. 11 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9:15 P Day 5 Month 12 Year 1978

The above well was plugged as follows:

RTD 3600' 8 5/8 csg set 216' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 7 1978

12-7-78

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-11-78
INV. NO. 8712-4

Signed: [Signature]
Well Plugging Supervisor