

KANSAS

Form CP-3  
Rev. 6-4-68



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20132-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
10-5-70

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas 67202

Lease Name Simmons Well No. 1

Location SE G ME NE Sec. 11 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3590'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling, Inc.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 12N Day 2 Month 10 Year 1970

The above well was plugged as follows:

Total Depth 3590' 8 5/8 csg set at 288' cwc 190 sk.

5 1/2 csg set at 3510' cw 125 sk cmt.

5 1/2 csg PBTD 3480' with top perf. (3098)

Set 5 1/2 wood plug at 3050. Poured 10' sand and dumped 5 sk cmt W/dump bailer. (3000-3050)

Cutoff and recovered 1426' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/4 sk hulls, -70 sk poz 6%, -10 sk gel,

plug and 50 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 10-5-70

INV. NO. 2629-U