

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,861-00-00 (of this well)

Operator's Full Name Brandt Oil Co.

Complete Address 1103 Douglas Bldg., Wichita, Kansas

Lease Name Lutz-Wiltrout Well No. 1

Location C E/2 SW NW Sec. 10 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 7 A Day 26 Month 11 Year 1978

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set 221' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

11-27-78
RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1978

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-29-78
INV. NO. 8633-W