

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20126-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Herndon Drilling Company

Complete Address: Box 489 Tulsa, Oklahoma

Lease Name Wiltrout Well No. 1

Location C NW NW Sec. 10 Twp. 6 Rge. 20 (E) (W) X

County Rooks Total Depth 3685

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 9P Day 28 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3685' 8 5/8 csg set at 248' cwc. Cmt. Mat. 50-50 pez cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 - 1968
CONSERVATION DIVISION
Wichita, Kansas

10-1-68

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/1/68
INV. NO. 8550-w

Signed: Leo J. Massey
Well Plugging Supervisor