

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 163-21, 210-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name GEODESSA CORPORATION

Complete Address 1125 - 17<sup>th</sup> St. # 2220 DENVER, COLORADO.

Lease Name NICHOLS Well No. "A" # 1

Location C-SW-SE Sec. 16 Twp. 6<sup>s</sup> Rge. 20<sup>w</sup> (East) (West)

County ROOFS Total Depth 3181

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated LOST HOLE

Plugging Contractor PIONEER DRILLING CO. INC.

Address 308 WEST MILL PLAINVILLE, MS License No. \_\_\_\_\_

Operation Completed: Hour: 8:40<sup>PM</sup> Day: 5 Month: JUNE Year: 19 81

The above well was plugged as follows:

8 5/8" 210<sup>ft</sup> SP. CUL 1/100<sup>st</sup> COMMON - 2% GEL. - 3% CA-CL.

ORDERED 110<sup>st</sup> COMMON - 2% GEL. - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HENY'S MUD BETWEEN ALL PLUGS.

LOST CIRCULATION @ 1120<sup>ft</sup> - CEMENTED @ 1150<sup>ft</sup> AND - 1700<sup>ft</sup>

1/250<sup>st</sup> COMMON - 2% GEL. - 3% CA-CL. - AND USED CAL-SEAL.

DRILLED TO 1700<sup>ft</sup> COULDN'T GET DOWN - GOT CIRCULATION BACK.

AND PLUGGED.

1<sup>st</sup> PLUG. @ 1080<sup>ft</sup> 1/65<sup>st</sup> ENT. RECEIVED 6-9-81

2<sup>ND</sup> PLUG. @ 240<sup>ft</sup> 1/30<sup>st</sup> ENT. STATE CORPORATION COMMISSION

3<sup>RD</sup> PLUG. - SOLID BRIDGE @ 40<sup>ft</sup> 1/10<sup>st</sup> ENT. JUN 10 1981

5<sup>th</sup> IN RPT HOLE (CEMENTED BY SUN OMT.) CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated. Wichita, Kansas

**INVOICED**

Signed: Marvin Schubert  
Conservation Division Agent

DATE 7-23-81

INV. NO. 5917-W