

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

AUG 3 1973

CONSERVATION DIVISION
Wichita, Kansas

8-3-73

15-163-20497-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pate-Dombaugh & Martin Exploration

Complete Address 502 Union Center, Wichita, Kansas

Lease Name Nichol Well No. 1

Location C NW NE Sec. 16 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3712'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.

Operation Completed: Hour 4:30 P Day 1 Month 8 Year 1973

The above well was plugged as follows:

RTD 3712' 8 5/8 csg set at 210' cwc 140 sk Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 8-3-73

INV. NO. 7709-W