

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-163-20453-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1972

CONSERVATION DIVISION
Wichita, Kansas

7-31-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C Oil, Inc.

Complete Address 842 Toh-n-hab Wichita, Kansas 67212

Lease Name Johnston Well No. 1

Location SW SW SE Sec. 24 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3800'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 8:45 P Day 29 Month 7 Year 1972

The above well was plugged as follows:

RTD 3800' 8 5/8 csg set at 209' cwc 140 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' & displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Res. F. Massey
Well Plugging Supervisor

INVOICED

DATE 8/1/72
INV. NO. 6089-W