

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20514-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
2-6-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name C Oil, Inc

Complete Address 842 Teh-N-Hah Wichita, Kansas

Lease Name Prebesce Well No. 1

Location NE NE NE Sec. 26 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3715' nn

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10 P Day 3 Month 2 Year 1974

The above well was plugged as follows:

RTD 3715' 8 5/8 csg set at 198' cwe 170 sk Cmt. Mat. 50-50 pez 6% gel.

Gunned pits, c reulated heavy mud, set cementing plug at 900' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mearns
Well Plugging Supervisor

INVOICED

DATE 2/8/74

INV. NO. 8545-W



15-163-20914-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
CONSERVATION DIVISION
Wichita, Kansas
2-6-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wagner of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: C Oil, Inc.

Complete Address: 842 Teh-N-Rah Wichita, Ks.

Lease Name: Probesee Well No. 1

Location: NE NE NE Sec. 26 Twp. 6 Rge. (E)(W) 20

County: Rooks Total Depth 3715' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace

70 sk cmt thru drill pipe. Heavy mud to 185' set cementig plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of wellar.

Very truly yours,

Leo F. Messy
Conservation Division Agent