

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21, 786-40600

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name PETX Petroleum Corporation 6278

Complete Address 1616 Glenarm Place, Denver, Colo. 80202

Lease Name Gartrell Well No. 3

Location NW NE SE Sec. 26 Twp. 6 Rge. 20 (East)(West)

County Rooks Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. and Allied Cementing Co., Inc.

Address 251 N. Water, Wichita, Kansas License No. 7

Operation Completed: Hour: 5 PM Day: 17 Month: September Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Anhydrite 1705-37'

Hole circulated and filled with mud. 100 sacks cement pumped through drill pipe at 1140'. 40 sacks cement pumped through drill pipe at 270'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50/50 Pozmix w/2% gel and 3% c.c.

Amount of Surface Casing: 8 3/8" - 250' - 175 sacks 60/40 Poz.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Busy in Rice County and Saline County

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 9-27-82

INV. NO. 1247-W