

*20*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20138-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11-22-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Bramum Oil Company  
Complete Address: Russell, Kansas  
Lease Name Wyrill (ROWNO) DA Well No. 1  
Location NW NW Sec. 29 Twp. 6 Rge. 20 (E)    (W) X  
County Rooks Total Depth 3735  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A XX  
Other well as hereafter indicated: Reenter (DA)  
Plugging Contractor: Peel Bros.  
Address: Hosington, Kansas License No.     
Operation Completed: Hour 3A Day 3 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3735' 8 5/8 csg set at 215' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sc cmt.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 11/22/68  
INV. NO. 8854-W

Signed: Leo F. Messy  
Well Plugging Supervisor