



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20138-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas
10-28-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Branum Oil Company

Complete Address: Russell, Kansas

Lease Name Wyrill Well No. 1

Location NW NW Sec. 29 Twp. 6 Rge. 20 (E) (W) X

County Rooks Total Depth 2265 ^{2270'}

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: Lost Hole

Plugging Contractor: Peel Bros.

Address: Hosington, Kansas License No.

Operation Completed: Hour 2:15P Day 23 Month 10 Year 1968

The Above well was plugged as follows:

RTD 2265 8 5/8 csg set at 215' cwc 240 sc.

Set 25 sc cmt plug W/1/4 CC (570-600) Thru drill pipe.

Set 25 sc 50-50 poz cmt plug at 570' thru drill pipe.

Set cementing plug, 1/2 sc hulls and 25 sc cement at 200'.

Mud to 40' 1/2 sc hulls and 10 sc cement to base of cellar.

Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/28/68
INV. NO. 8900-11

Signed: Leo F. Massey
Well Plugging Supervisor