

KANSAS

JC
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20091-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1968
CONSERVATION DIVISION
Wichita, Kansas

1-29-68

Operator's Full Name L. J. Dreiling & Sons, Inc.

Complete Address Victoria, Kansas

Lease Name Benoit Well No. 1

Location NW NW SW Sec. 29 Twp. 6 Rge. 20 (E) (W) X

County Rooks Total Depth 3840

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4 P Day 23 Month 1 Year 1968

The above well was plugged as follows:

RTD 3840' (100 sc)
8 5/8 csg set at 151' cwc 100 sc. Cem. Mat. 50-50 poz cem. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1/29/68

INV. NO. 7155-W