

LEASE NAME Sarmons

WELL NUMBER 3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1,650 Ft. from S Section Line

1,980 Ft. from E Section Line

SEC. 29 TWP. 6 RGE. 20 (E) or (W)

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 east 30th. Hays, Kansas 67601

PHONE# (913) 625-5891 OPERATORS LICENSE NO. 7076

COUNTY Rooks

Character of Well oil

Date Well Completed 6-24-84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 10-11-85

Plugging Completed 11-26-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? #6 - Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation K.C. Depth to Top 3504' Bottom 3712' T.D. 3755'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
K.C.	oil & water	3504	3712	8 5/8	305	None
				4 1/2	3811'	1200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set Packer at 3400' and squeeze all zones to T.D. with 400 sacks cement - Pull 1200' of 4 1/2" - pump down 8 5/8" with 50 sacks cement - 1 sack hulls = 20 sacks gel w/2 sacks hulls = 100 sacks cement with 2 hulls = 10 sacks gel with 1 sack hulls = 1-8 5/8 wiper plug = 50 sacks cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ostrom Well Service License No. 5680

Address Route 1 - Plainville, Ks 67663

STATE OF KANSAS COUNTY OF ELLIS, ss.

LeRoy Berland (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) LeRoy Berland

(Address) 1105 E. 30th. #A. Hays, Ks. 67601

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 19 86

Robert K. McDowell
 Notary Public

My Commission Expires: 8/11/89



RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1986

CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 08-84

1-24-86