

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,348-06-00

LEASE NAME Sammons B

WELL NUMBER 01

SPOT LOCATION SW, NE, SE

SEC. 29 TWP. 6 RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 4-19-84

Plugging Commenced 4-19-84

Plugging Completed 4-19-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 E. 30th, Suite A; Hays Ks. 67601

PHONE # (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays Office

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

First plug at 3724' w/20 sacks
Second plug at 1860' w/20 sacks
Third plug at 1148' w/100 sacks & one sack floseal
Fourth plug at 308' w/40 sacks
Fifth plug at 40' w/10 sacks, one solid bridge plug
Plugged rat hole w/10 sacks -one sack hulls

Total- 200 sacks 50/50 poz, 6% gel
3% CC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R. and C. Drilling Company, Inc. License No. 9087
Address 2717 Canal, P.O. Box 296; Hays, Ks. 67601

STATE OF Kansas COUNTY OF Ellis, ss.

John Weis (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
4-30-84
APR 30 1984

(Signature) John Weis
(Address) P.O. Box 296
2717 Canal; Hays, Ks. 67601



SUBSCRIBED AND SWORN TO before me this 26 day of April, 1984

Angela F. Zumbaugh
Notary Public

My Commission expires: 12-16-87