

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-02555-00-00
Spot: NWNSW Sec/Twnshp/Rge: 23-23S-4W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: BLAKE Well #: 6
County: RENO Total Vertical Depth: 3614 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

COND Size: 16 feet: 257 225 SX CMT
PROD Size: 5.5 feet: 3465 50 SX CMT
PROD Size: 7 feet: 3585 500 SX CMT
SURF Size: 13 feet: 506 200 SX CMT

11746

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2004 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: DAVID M WILSON Company: _____ Phone: (918) 492-9797

Proposed Plugging Method: DUMP 35 SX SAND THEN SPOT 5 SX CMT @ 2750'. SPOT 35 SX CMT @ 550'. PERFORATE @ 350' AND CIRCULATE CMT ON BACKSIDE. CASING COLLAPSED @ 2893'.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 11/02/2004 2:30 PM KCC Agent: MICHAEL WILSON

RECEIVED
KCC DISTRICT #2
JAN 21 2005
WICHITA, KS

Actual Plugging Report:

Pipe collapsed at 2,605'. Sanded to 2,450' & topped with 5 sxs. cement. Perforated casing @ 350'. Ran tubing to 550' & spotted 35 sxs. cement. Pulled tubing to 350' & circulated 120 sxs. cement to the surface. Pulled tubing & hooked onto 5 1/2" casing. Circulated 80 sxs. cement inside & outside 5 1/2" casing to the surface.

Perfs:

RECEIVED
FEB 28 2005
KCC WICHITA

Remarks: USED 60/40 POSMIX W/4% GEL BY

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 3-1-05
INV. NO. 2005061229