

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21011-00-01
Spot: NENESENW Sec/Twnshp/Rge: 17-25S-5E
3655 feet from S Section Line, 2790 feet from E Section Line
Lease Name: L W ROBISON NORTH Well #: 3B
County: BUTLER Total Vertical Depth: 2500 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: ONE NORTH HUDSON, SIXTH FLOOR
OKLAHOMA CITY, OK 73102

PROD Size: 4.5 feet: 798 50 SX CMT
SURF Size: 8.625 feet: 207 150 SX CMT

81²⁵

Well Type: EOR UIC Docket No: E21399.1 Date/Time to Plug: 01/20/2005 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY COMPANY Phone: (316) 321-0550

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Ran 1" to 750' in 4-1/2" and circulated to surface with 45 sacks of cement. Ran 1" between 4-1/2" and 8-5/8" to 250' and circulated cement to surface with 65 sacks of cement.

United Cementing

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
705	718		RECEIVED KCC DISTRICT #2 FEB 18 2005 WICHITA, KS


RECEIVED
FEB 28 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 3-1-05
2005061228