

3 022686

15-207.19472.00.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

SE,NW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

1895 feet from south section line

4380 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# APT NO. 23

Operator License # 101

County WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 1000' feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2" Size Feet 1000'

Address

Surface Casing: 8" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 27 Month: 1 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 12:00P.M. Day: 27 Month: 1 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

86 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

FEB 09 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 23) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN