

6 090194

P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,575-00-00
SE 1/4, SEC. 27, T. 6 S., R. 20 W. 10
1650 feet from N/S section line
990 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Ross Well # 9-27

Operator: Murphy Drilling Company
Name & Address 250 N. Water, Suite 300
Wichita, Kan. 67202

County Rooks
Well Total Depth 3750 121-88 feet
Conductor Pipe: Size - feet -
Surface Casing: Size 8 5/8 feet 252 V

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor Murphy Drilling Company License Number 6033
Address 250 N. Water, Suite 300 Wichita, Kan. 67202

Company to plug at: Hour: - Day: 8 Month: December Year: 19 84

Plugging proposal received from Steve Carlton

(company name) Murphy Drilling Company (phone) 316-267-3241

were: Order 200 sbs. 50/50 procut, 6% gel, 3% Cal. Cl. + 8 5/8" virgin plug, spot all plugs through drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All - Part - None

Operations Completed: Hour: 12:30 PM Day: 8 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug 3690' w/ 20 sbs.

2nd plug 1765' w/ 20 sbs.

3rd plug 1060' w/ 1 sb. Alb. Flake + 100 sbs.

4th plug 300' w/ 40 sbs.

5th plug 40' solid bridge 1 sb. Buller + 10 sbs.
10 sbs. in rat hole.

12-17-84
RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation - 2160', Arhydrite - 1759', Arbuckle - 3686' (Hullburton)
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Edwin A. Schumacher
(TECHNICIAN)

DATE 1-3-85

INV. NO. 6790

12-8 JAN 14 1985

12-13-84
FORM CP-2/3
Rev. 01-84