

6 070255

15-163-01013-00-01

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION NW-NW-SW, SEC. 30, T. 6 S, R 20 @ 16 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

API NUMBER 15-163-01-013-00-01

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name VOSS Well # 1 (OUUO)

Operator: FRONTIER OIL COMPANY Name & Address 1720 KANSAS STATE BK. BLDG. WICHITA, KANSAS 67202

County ROOMS. 124.80

Well Total Depth 3840 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 182

Abandoned Oil Well Gas Well Input Well SWD Well (D&A (OUUO))

Other well as hereinafter indicated RE-ENTRY - (OUUO) DRY # TAG-79

Plugging Contractor RED TIGER DRILLING CO. License Number 5302

Address WICHITA, KS. 6720

Company to plug at: Hour: 3:45 PM Day: 17th Month: NOV. Year: 1984

Plugging proposal received from WALT ODEN

(company name) RED TIGER DRILLING (phone) 316-265-1201

were: 8 5/8" - 182' SP. # CUC. AMOUNT UNKNOWN.

ORDERED 230 SK 50/50 FORMIX GEL - CA-CL - 1 SK 710 CELE AND 8 5/8" CUC.

SPOTTED WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, FLV. 2265 - AMH. 1870 - ARBUCKLE 3818

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 PM Day: 17th Month: NOV Year: 1984

ACTUAL PLUGGING REPORT ORDERED 230 SK 50/50 FORMIX GEL - CA-CL - 1 SK 710 CELE AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 3780 FT #/30 SK CNT, 2nd PLUG @ 1890 FT #/30 SK CNT

3rd PLUG @ 1160 FT #/100 SK CNT #/1 SK 710 CELE, 4th PLUG @ 270 FT #/50 SK CNT

5th PLUG SOLID BRIDGE PLUG @ 40 FT #/10 SK CNT - 10 SK IN ENT GBLE

CEMENTED BY ALLIED CNT.

Remarks: (If additional description is necessary, use BACK of this form.)

NOV 25 1984 11-26-84 CONSERVATION DIVISION WICHITA, KANSAS

INVOICED

DATE 11-28-84

IN. NO. 4967

Signed [Signature] (TECHNICIAN) 11-21-84

11-17 JAN 1 4 1985

FORM CP-2/3 Rev. 01-84