

6-050149

12-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-22,369 ~~000~~
SW SW NW /4 SEC. 29, 6 S, 20 W
2970 feet from S section line
4950 feet from E section line

Operator license# 7076 Lease Sammons A well # 1

Operator: Black Diamond Oil, Inc. County Rooks

Address: P. O. Box 641 Well total depth 3757 feet
Hays, Kansas 67601 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 259 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Co., Inc. License#

Address: P. O. Box 31, Russell, Kansas 67665

Company to plug at: Hour: AM Day: 20 Month: December Year: 1994

Plugging proposal received from: Ken Vehige

Company: Black Diamond Oil phone: 913-625-5891

Were: 4 1/2" set at 3728' w 125 sx. Port collar at 1888' with 650 sx.
TOC at 630', perfed at 625', pumped 650 sx. Circ cement. Production
perfs at 3515' to 3656'. Orders were to bull squeeze 190 sx 60/40 poz
10% gel down 4 1/2" casing. Squeeze 8 5/8" X 4 1/2" annulus with 50 sx
60/40 poz, 10%.

Plugging Proposal Received by: Bruce Basye
Plugging operations attended by agent? All[], Part[], None[XXX]

Completed: Hour: 10:30 AM, Day: 20, Month: December, Year: 1994

Actual plugging report: Bull squeezed 210 sx 60/40 poz, 10% gel down
4 1/2" casing. Maximum pressure at 1100#, shut in at 800#.
8 5/8" X 4 1/2" casing squeezed with 0 sx cement, pressure to 600#.

Remarks: Condition of casing(in hole): GOOD XX BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC XX, NO Dakota plug: YES XX, NO
Plugged through TUBING , CASING XX Elevation: 2245 GL

I did did not [XXX] observe the plugging.

INVOICED
DATE 1-3-95
INV. NO. 41945
12-20

DEC 27 1994
12-27-94
DIVISION
WICHITA, KANSAS
Bruce D. Basye
(agent)