

6030442

R

API NUMBER 15-163-22,677-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NENE, SEC. 29, T. 6 S, R. 20 W

4950 feet from RS section line

330 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Wysell Farms Well # 1

Operator: A. Scott Ritchie

County Rooks 123.02

Name & Address 125 N. Market, Ste. 950

Well Total Depth 3785 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 3/8 feet 200'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilg. Co. License Number 6033

Address Wichita, Kansas.

Company to plug at: Hour: AM Day: 11 Month: 5 Year: 19 85

Plugging proposal received from Schieferash

(company name) Murfin Drilg. Co. (phone) _____

were: 8 3/8 at @ 200' w/ 180at with hole full of no less than 36 lbs. mud and no loss of fluid spot cement plugs with 1/2" D.P. order 205 at. 5050 pp 6 1/2 03 1/2 w. 8 3/8 W.P. Allied Cement Co.

MAY 28 1985 5-28-85

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45AM Day: 11 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT Spot D.P. @ 3775 displace 25 at Cem. mix. laydown

D.P. to 1850 displace 25 at Cem. mix. laydown D.P. to 1100' displace

90 at Cem. mix. + 1 at Cello Flake laydown D.P. to 225' displace 40 at

Cement mix. laydown D.P. Push 8 3/8 W.P. to Kelly depth fill hole with Cem.

mix from plug to bottom Cellar 10 at. displace 15 at Cem. mix in rathole

with a joint of pipe

Remarks: Elev. 2226 Ch. Anhy. 1830-59 at 3730 elev 30,000 Pond water.
(If additional description is necessary, use BACK of this form.)

INVOICE RECEIVED
I hereby acknowledge and observe this plugging.

DATE 6-6-85

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 8390

7
5-28-85
ms

5-11 JUN 12 1985