

15-163-202 02-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WELL #1
SW NW SW Section 29-88-20W
Rocks County, Kansas

Commenced: March 31, 1969
Completed: April 8, 1969

OPERATOR - J. Mark Richardson

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1969
CONSERVATION DIVISION
Wichita, Kansas

DEPTH		FORMATION	REMARKS
From	To		
0	140	Surface clay and sand	
140	302	Shale	
302	466	Shale and sand	Run 26 joints 8-5/8" casing, set @ 466' w/centralizer @ 448' cemented w/50 sacks on bottom and 225 sacks on top. Cemented w/200 sacks cement around pipe from top thru 1" @ 100'.
466	1700	Shale and sand	
1700	1855	Shale	
1855	1890	Anhydrite	
1890	2045	Shale	
2045	2365	Shale and shells	
2365	3500	Shale and lime	
3500	3740	Lime	
3740	TD		Run 103 joints 8-1/2" casing, set @ 3739' w/100 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW NW SW Section 29-88-20W, Rocks County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 15 day of April, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

