

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 163-21,154 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date November 1980

Well Operator: Shelby Resources, LLC KCC License #: 31725
(Owner / Company Name) (Operator's)

Address: 5893 Saddle Creek Trail City: Parker

State: Colorado Zip Code: 80134 Contact Phone: (303) 840 - 2183

Lease: Lowry Well #: 3 Sec. 20 Twp. 8 S. R. 19 East West

S/2 - SE - NW - SW Spot Location / QQQQ County: Rooks

1320' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 286' Cemented with: 160 Sacks

Production Casing Size: 4-1/2" Set at: 3431' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations 3217-22'. In 1984, a casing leak was repaired @ 935' (150 sxs). In 1989, a casing leak was repaired @ 934' (125 sxs).

Elevation: 1984 (G.L. / K.B.) T.D.: 3435' P.BTD: 3229' Anhydrite Depth: 1462-1498
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Bring out 225 sxs. 60/40 poz with 10% gel & 500# hulls. RIH with tubing to +/- 2000'. Circulate cement to surface. Pull tubing a squeeze casing to 1500#. Tie on to annulus and fill backside with cement. Pressure up to 500#.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log and ACO-1 are not available.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Brian Karlin

Address: P.O. Box 1213 Phone: (785) 623 - 3290

City / State: Hays, Kansas 67601

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____

Address: P.O. Box 31, Russell, Kansas 67665-0031 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): Not available

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 03-07-2005 Authorized Operator / Agent: Brian Karlin
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 10 2005

KCC WICHITA

Brian

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Shelby Resources LLC
5893 Saddle Creek Trail
Parker, CO 80134

March 10, 2005

Re: LOWRY #3
API 15-163-21154-00-00
S2SENWSW 20-8S-19W, 1320 FSL 990 FWL
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor