

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1
Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-095-21947-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation (owner/company name) KCC LICENSE # 5003 6/05
(operator's)

ADDRESS: 8080 E. Central, Suite 300 CITY: Wichita
STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737
LEASE: Holgerson-Twyman WELL#: 3-3 Section 3 Township 30s Range 9w
30' W of NW NE SPOT LOCATION/QQQQ COUNTY: Kingman
660 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)
2010 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 226' KB CEMENTED WITH 250 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1607 G.L. 1616 K.B. T.D. 4340 PBDT _____ Anhydrite Depth _____
(Stone Corral Formation)
CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugging orders received from Greg Eves at 4:00 pm on 03/02/05. Plugged hole using 135 sx 60/40 Poz,
6% Gel as follows: Heavy mud in hole, Bottom plug 35 sx @ 1400', then 35 sx @ 950', then 65 sx @ 276',
topped off with 10 sx @ surface. Intervals between plugs are heavy mud. Plugged Rathole with 15 sx
and mousehole with 10 sx. Job completed at 2:45 am on 03/05/05 by Acid Services. Ticket # 9688. Sterling reported to KCC on 03/07/05.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why: _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Lanny Saloga/Gary M. Talbott Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142 6/05
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Finished plugging well at 3:30 am on March 5, 2005.
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 03/05/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED
MAR 09 2005
KCC WICHITA
Bu

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Holgerson-Twyman 3-3

LOCATION: 30' W of NW NE
API: 15-095-21947-0000

Section 3 T 30s R 9w
Kingman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 02/24/05
COMPLETED: 03/05/05

TOTAL DEPTH:	DRILLER	4340	FEET
	LOGGER	4338	FEET

Ground Elevation: 1607
KB Elevation: 1616

LOG

0 -	2 FEET	Top Soil
2 -	185 FEET	Sand, Gravel and Clays
185 -	80 FEET	Redbeds
80 -	1320 FEET	Shales and Salt
1320 -	4340 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 1:00 pm on 02/24/05. Drilled 12-1/4" hole to 230'. Ran 5 joints of new 23# 8-5/8" surface casing tally 215.29' set at 226.29' KB. Cemented with 250 sx 60/40 Poz; 2% Gel, 3% CC, & 1/4#/sx Celloflake. Plug down at 8:15 pm on 02/24/05 by Acid Services, ticket #10001. Cement did circulate. Welded straps on bottom 3 jts, of SP, then tacked collars on next 2 joints.

Production Casing:

Plugging orders received from Greg Eves at 4:00 pm on 03/02/05. Plugged hole using 135 sx 60/40 Poz, 6% Gel as follows: Heavy mud in hole, Bottom plug 35 sx @ 1400', then 35 sx @ 950', then 65 sx @ 276', topped off with 10 sx @ surface. Intervals between plugs are heavy mud. Plugged Rathole with 15 sx and mousehole with 10 sx. Job completed at 2:45 am on 03/05/05 by Acid Services. Ticket # 9688. Sterling Drilling reported plugging to KCC District 2 on 03/07/05

DEVIATION SURVEYS

3/4 degree(s) at	230	feet
1 degree(s) at	4238	feet

RECEIVED
MAR 09 2005
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

McCoy Petroleum Corporation
8080 E. Central, Suite 300
Wichita, KS 67206

March 09, 2005

Re: HOLGERSON TWYMAN #3-3
API 15-095-21947-00-00
NWNE 3-30S-9W, 660 FNL 2010 FEL
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



David P. Williams
Production Supervisor