

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-21947-0000
LEASE NAME Holgerson-Twyman
WELL NUMBER 3-3

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

660 Ft. from North Line of Section
2010 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation **5003** SPOT LOCATION 30' W of NW NE
ADDRESS 8080 E. Central, Suite 300 Section 3 Township 30s Range 9w
CITY, STATE, ZIP Wichita, Kansas 67206 County Kingman
PHONE # 316-636-2737 Date Well Completed 03/05/05
Character of Well Dry and Abandoned Date Plugging Commenced 03/05/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 03/05/05

The plugging proposal was approved on March 2, 2005 at 4:00 pm (date)
by Greg Eves (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	168			0
Redbeds	Shale	168	230	8-5/8"	226	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugging orders received from Greg Eves at 4:00 pm on 03/02/05. Plugged hole using 135 sx 60/40 Poz,
6% Gel as follows: Heavy mud in hole, Bottom plug 35 sx @ 1400', then 35 sx @ 950', then 65 sx @ 276',
topped off with 10 sx @ surface. Intervals between plugs are heavy mud. Plugged Rathole with 15 sx
and mousehole with 10 sx. Job completed at 2:45 am on 03/05/05 by Acid Services. Ticket # 9688. Sterling reported to KCC on 03/07/05.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 8th day of March, 2005



Pamela S. Fields
(Notary Public)

RECEIVED

MAR 09 2005

KCC WICHITA

My Commission Expires: _____

Form CP-4
Revised 12-92

B

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Holgerson-Twyman 3-3

LOCATION: 30' W of NW NE
API: 15-095-21947-0000

Section 3 T 30s R 9w
Kingman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 02/24/05
COMPLETED: 03/05/05

TOTAL DEPTH:	DRILLER	4340	FEET
	LOGGER	4338	FEET

Ground Elevation: 1607
KB Elevation: 1616

LOG

0 -	2 FEET	Top Soil
2 -	185 FEET	Sand, Gravel and Clays
185 -	80 FEET	Redbeds
80 -	1320 FEET	Shales and Salt
1320 -	4340 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 1:00 pm on 02/24/05. Drilled 12-1/4" hole to 230'. Ran 5 joints of new 23# 8-5/8" surface casing tally 215.29' set at 226.29' KB. Cemented with 250 sx 60/40 Poz; 2% Gel, 3% CC, & 1/4#/sx Celloflake. Plug down at 8:15 pm on 02/24/05 by Acid Services, ticket #10001. Cement did circulate. Welded straps on bottom 3 jts, of SP, then tacked collars on next 2 joints.

Production Casing:

Plugging orders received from Greg Eves at 4:00 pm on 03/02/05. Plugged hole using 135 sx 60/40 Poz, 6% Gel as follows: Heavy mud in hole, Bottom plug 35 sx @ 1400', then 35 sx @ 950', then 65 sx @ 276', topped off with 10 sx @ surface. Intervals between plugs are heavy mud. Plugged Rathole with 15 sx and mousehole with 10 sx. Job completed at 2:45 am on 03/05/05 by Acid Services. Ticket # 9688. Sterling Drilling reported plugging to KCC District 2 on 03/07/05

DEVIATION SURVEYS

3/4 degree(s) at	230	feet
1 degree(s) at	4238	feet

RECEIVED
MAR 09 2005
KCC WICHITA