

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20489-00-01
Spot: SENW Sec/Twnshp/Rge: 13-33S-43W
1998 feet from N Section Line, 1966 feet from W Section Line
Lease Name: WINTER MORROW UNIT Well #: 101
County: MORTON Total Vertical Depth: 5725 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 5570 WITH 2 SX CMT
PROD Size: 5.5 feet: 4799
SURF Size: feet: 1357

06
A/86

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2004 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PLUG AT 2380' WITH 100 SX CMT. PLUG AT 1380' WITH 75 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE
Date/Time Plugging Completed: 08/07/2004 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:


1ST PLUG SET CIBP @ 5570' & 2 SX CMT. 2ND PLUG FREE POINT CASING AT 2406'. SHOT OFF. CIRCULATE HOLE WITH DRILLING MUD, THEN PUMP 100 SX CLASS H CMT. TOC @ 2290'. 3RD PLUG RE-CEMENT 2 MORE TIMES TO ESTABLISH KICK-OFF POINT. DRILLED NEW HOLE TO 5725'. LOST CIRCULATION- STUCK DRILL PIPE. FREE POINT DRILL PIPE @ 2394'. BACK OFF DRILL PIPE @ 2394'. 4TH PLUG PUMP 100 SX CMT @ 2380'. TOC @ 1851'. 5TH PLUG PUMP 75 SX CMT AT 1380'. TOC @ 979'. 6TH PLUG PUMP 40 SX CMT @ 600'. TOC @ 384'. 7TH PLUG PUMP 10 SX CMT AT 40-0'. 8TH PLUG PUMP 15 SX CMT IN RAT HOLE & 10 SX CMT IN MOUSE HOLE.

RECEIVED
FEB 09 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SCHLUMBERGER.

Plugged through: CSG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 2-9-05

NO. 2005061173