

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20699-00-00
Spot: NESESW Sec/Twnshp/Rge: 25-9S-33W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ROSS A Well #: 1-25
County: THOMAS Total Vertical Depth: 4735 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

SURF Size: 8.625 feet: 416

\$153.⁸⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/02/2005 12:15 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 636-2737

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE
Date/Time Plugging Completed: 02/02/2005 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 2725' w/25 sxs. (Mid Anhydrite).
2nd. Plug at 1845' w/100 sxs. (Dakota).
3rd. Plug at 470' w/40 sxs.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
15 sxs Rathole.
10 sxs Mousehole.
Total of 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

RECEIVED
FEB 10 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMMpany.

Plugged through: DP

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED

DATE 2-10-05

INV. NO 2005061176

Form CP-2/3

FEB 08 2005

10