

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23104-00-00
Spot: NWNESW Sec/Twnshp/Rge: 30-21S-11W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: DUGGAN Well #: 2
County: STAFFORD Total Vertical Depth: 3649 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: P.O. BOX 1469
PLAINFIELD, IL 60544

PROD Size: 5.5 feet: 3644 WITH 175 SX CMT
SURF Size: 8.625 feet: 549 WITH 325 SX CMT

#118⁵⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2005 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 50' ABOVE PERFS & 4 SX CMT. PLUG AT 580' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK
Date/Time Plugging Completed: 02/10/2005 2:25 PM

WitnessType: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3620'. TOC @ 2769'. ANHYDRITE TOP = 539'. SANDED BOTTOM TO 3490' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 580' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3576	3582		
3560	3566		
3544	3552		

RECEIVED
FEB 16 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2250' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED
DATE 2-16-05
INV. NO. 2005061197

Form SP-213