

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21485-00-00
Spot: SESWNWSW Sec/Twnshp/Rge: 4-29S-15W
1400 feet from S Section Line, 4890 feet from E Section Line
Lease Name: BOLSER RG Well #: 3
County: PRATT Total Vertical Depth: 4823 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S. MAIN, STE 420
WICHITA, KS 67202

PROD Size: 5.5 feet: 4818 WITH 300 SX CMT
SURF Size: 8.625 feet: 432 WITH 250 SX CMT

A/S6 95

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2005 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4640' & 5 SX CMT. PLUG AT 930' WITH 15 SX GEL 50 SX CMT & 100# HULLS. PLUG AT 460' WITH 50 SX CMT & 100# HULLS. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2005 12:34 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4640' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUG THROUGH CASING WHILE PULLING. 1ST PLUG AT 930' WITH 15 SX GEL - 50 SX CMT W/100# HULLS. 2ND PLUG AT 460' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4694	4710		

RECEIVED
FEB 16 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BYALLIED. RECOVERED 2520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 2-16-05
INV. NO. 2005061191

Form CP-2/3
[Signature]