

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22341-00-00  
Spot: NWNW Sec/Twnshp/Rge: 10-32S-39W  
724 feet from N Section Line, 684 feet from W Section Line  
Lease Name: MLP CLOSE B Well #: 1  
County: STEVENS Total Vertical Depth: 6035 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

PROD Size: 5.5 feet: 6028 WITH 125 SX CMT  
SURF Size: 8.625 feet: 1737 WITH 460 SX CMT

#196<sup>14</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2005 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLA & 25 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2005 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PORT COLLAR @ 3051'. PUMP 400# HULLS & 25 SX CMT. DISPLACE WITH MUD. PRESSURE TO 500# & HELD. 1ST PLUG PULL OUT OF HOLE TO 1750'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE WITH MUD & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5856	5885		

RECEIVED  
FEB 16 2005  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1892' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 2-16-05  
INV. NO. 2005061193

Form PR-23