

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22304-00-00
Spot: SWSESENW Sec/Twnshp/Rge: 31-31S-38W
2323 feet from N Section Line, 2205 feet from W Section Line
Lease Name: MLP CAVNER D Well #: 1
County: STEVENS Total Vertical Depth: 6125 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

COND Size: 20 feet: 40 NO RECORD
MSCC Size: feet: 2999
PROD Size: 5.5 feet: 6110 WITH 395 SX CMT
SURF Size: 8.625 feet: 1625 WITH 450 SX CMT

#199⁰⁶

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/26/2005 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS WITH 25 SX CMT PLUG AT 1530' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2005 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 400# HULLS WITH 25 SX CMT. DISPLACE WITH MUD. PRESSURE TO 500# & HELD. 1ST PLUG LOAD HOLE WITH MUD & PUMP 50 SX CMT AT 1400'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
6002	6011		

RECEIVED
FEB 16 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 2-16-05
INV. NO. 2005061193