

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21861-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 30-23S-33W  
2331 feet from N Section Line, 330 feet from W Section Line  
Lease Name: GCC Well #: 1-530  
County: FINNEY Total Vertical Depth: 4810 feet

Operator License No.: 32309  
Op Name: PRESCO WESTERN LLC  
Address: 1775 SHERMAN STE 2950  
DENVER, CO 80203

SURF Size: 8.625 feet: 1725

*\$156<sup>33</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/20/2005 6:30 AM  
Plug Co. License No.: 33375 Plug Co. Name: CHEYENNE DRILLING, LP  
Proposal Revd. from: RODNEY Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 1ST PLUG AT 3100' WITH 100 SX CMT. 2ND PLUG AT 1750' WITH 50 SX CMT. 3RD PLUG AT 1100' WITH 50 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE  
Date/Time Plugging Completed: 01/20/2005 9:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:


1ST PLUG AT 3100' WITH 100 SX CMT. 2ND PLUG AT 1750' WITH 50 SX CMT. 3RD PLUG AT 1100' WITH 80 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
FEB 16 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

*James D Holland*  
(TECHNICIAN)

*PART II*

INVOICED  
DATE 2-16-05  
INV. NO. 2005061194

Form CP-23